MOBILE DRILL BRAIN

Calibration Technician Training Module 007

Report Handoff, Field Closeout, and Customer Relationship Notes

Field	Value
Document type	Workspace 006-B technician training module
Module	007 - Report Handoff, Field Closeout, and Customer Relationship Notes
Version	v0.1 Deliverable
Prepared	July 2026
Source basis	Calibration Service Module Extraction Worksheet v0.1; Calibration Data Collection Cheat Sheet; Modules 001-006; user SME field-handoff corrections
Training lane	Calibration Technician Training - field closeout and report-builder handoff
Status	Internal training draft - not a final field SOP, customer report, or analyzer manufacturer manual

Locked module purpose

Teach the calibration technician how to close out the field portion of a calibration event, preserve complete report-builder information, transfer analyzer data, document field exceptions, and close the customer interaction professionally without overpromising report results or timing beyond approved standards.

Core rule
A calibration job is not complete just because the analyzer recorded data. It is complete when the data files, calibration log, field notes, exceptions, and handoff path are clear enough for the qualified report builder to complete the report without guessing.

1. Source basis and training boundary

This module uses the calibration extraction worksheet for report package structure, status workflow, report-builder handoff, do-not-promise rules, and field documentation requirements. It uses the calibration data collection cheat sheet for end-test behavior, saved-file review, repeated interval logic, LP/LE file context, and data closeout. It also uses Modules 004-006 for software workflow, measurement accuracy, data quality, refusal, sensor issues, and escalation boundaries.

2. Training boundary

This module does not teach the standard technician to build, review, approve, or deliver the final calibration report. Final report building and customer delivery are performed only by qualified report builders. For current Mobile Drill training, Jonathon and Charlie are the qualified report builders and follow the same report-building standards.

Boundary statement
The field technician collects and hands off complete, reviewable information. The report builder turns that information into the formal calibration report package.

3. Learning outcomes

1. Explain what report handoff means and why it matters.
2. End a data collection run correctly and understand when analyzer data becomes reviewable.
3. Transfer or hand off analyzer data by an approved method.
4. Complete and protect the calibration log: one sheet per rig.

5. Verify that saved files and handwritten notes match depth interval, sample interval, LP, LE, and blow-count records.
6. Document refusal, rapid advancement, reruns, questionable data, sensor changes, and other field obscurities.
7. Identify when photo or video documentation is useful or required.
8. Explain the report package at an awareness level without trying to build the report.
9. Explain the status workflow from data collection through customer delivery.
10. Close the customer interaction professionally and capture relationship/prospecting notes without overpromising.

4. What report handoff means

Report handoff has three lanes. A tech must complete all three before the job is truly closed from the field side.

Lane	What it includes	Why it matters
Technical handoff	Analyzer data files, calibration log, depth intervals, LP, LE, sample interval, blow counts, photos/video when needed, and field notes.	The report builder needs the complete record, not just analyzer pages.
Report-builder readiness	Clear explanation of anything unusual, missing, rerun, questionable, or project-driven.	Missing context can delay the three-day report delivery standard.
Customer relationship closeout	Thank drillers and manager, gather tooling wish list, hand out shirts when appropriate, and listen for business/prospecting signals.	Calibration work is also a relationship-building and sales-intelligence opportunity.

5. End-of-test closeout

At the end of each active data collection run, the tech must end the test properly so the data file is saved and available for review.

11. End active collection using the play button after the collection interval is complete.
12. When the End Test box appears, hit Yes.
13. Confirm the data file becomes available for review.
14. If the data looked questionable, preserve the file and document the issue rather than hiding or ignoring it.
15. Repeat the required setup and field documentation checks for each additional interval or rig.

Training rule
Hit Yes on End Test even if the data was not clean. Saving the file makes it available for review, documentation, rerun comparison, or troubleshooting.

6. Analyzer data handoff

All calibration data remains stored on the SPT analyzer hardware. The handoff method depends on customer need, report timing, travel, and whether the tech is returning to the office.

Handoff method	When used	Training note
USB export to work laptop and email to report builder	Most common and easiest path when report turnaround or customer need requires quick handoff.	Export from the hardware unit, move to work laptop, and email directly to the report builder.
Physical handoff in office	Used when the tech returns to the office or when direct device/file handoff is easier.	Make sure the report builder knows what rig/customer/event the files belong to.
Other practical handoff as directed	Used when timing, travel, customer urgency, or technical constraints require another approved path.	The goal is complete report-builder access within the report delivery expectation.

Three-day report standard
The standard customer delivery expectation is three days from data collection. Handoff speed should support that promise.

7. Calibration log - one sheet per rig

The paper form used for field handoff is the calibration log. Use one single sheet per rig.

Calibration log item	What the tech records	Why it matters
Customer / rig identity	Customer name, rig model, rig serial number, borehole ID, date, operator/driller, tech.	Ties field notes and analyzer files to the correct report.
Depth and sample interval	Start and end depth in feet; 18-inch or 24-inch interval as actually collected.	Prevents mismatch between software file context and field reality.
LP and LE	LP and measured LE for each data set.	Report builder needs correct measurement context for each run.
6-inch blow counts	Every 6-inch increment recorded on paper.	Software total is not enough for report building and refusal awareness.
Field notes / exceptions	Refusal, rapid advancement, reruns, project interval requirements, sensor issues, odd hammer behavior, or other obscurities.	Explains data quality and prevents delay when report builder was not on site.

8. File and field-record consistency check

Before the tech considers a rig complete, the saved analyzer files and calibration log should tell the same story.

- The rig identity in the software/file context matches the rig being reported.
- The depth interval in the software matches the actual sample interval.
- LP and LE are recorded for each interval.
- LE was measured, not assumed.
- The paper blow-count breakdown exists for every 6-inch increment.
- Refusal, rapid advancement, reruns, and questionable data are documented.
- Any changed sample interval or production-driven interval requirement is explained.
- Any sensor replacement, cable problem, accelerometer issue, or suspected equipment damage is documented.

9. Photos and video documentation

Media type	When to capture	Handoff use
Good rig/location photos	Useful when the rig is on location and the site/rig setup is visually useful.	Marketing, relationship building, internal context, and future customer familiarity.
Video of weird issues	Preferred when something unusual occurs.	Helps report builder or senior tech understand the issue.
Required video	Required when the issue affects calibration data.	Supports data-quality review and escalation.

Training rule
Photos are helpful. Video becomes more important when the issue affects calibration data or cannot be explained clearly in notes.

10. Field notes and obscurities

Field notes protect the report builder. If the report builder was not standing next to the rig, the notes must explain what happened.

- Refusal or incomplete advancement.
- Rapid advancement or loose soil that required stopping or changing approach.

- Reruns and why they were performed.
- Questionable data and what checks were performed.
- Sensor, accelerometer, cable, connector, or pulse-check issue.
- Accelerometer replacement or backup sensor use.
- Suspected strain gauge issue or instrumented rod concern.
- Hammer behavior issue such as cycling, idle/RPM concern, short stroke, leaks, or hydraulic concern.
- Project sampling requirement that forced a different interval or frequency.
- Any customer/driller pressure or production constraint that affected the calibration workflow.

11. Report package awareness

The field tech does not build the final report in this module, but should understand what the report builder is trying to complete.

Report package component	Purpose / what it represents	Field-tech connection
Cover page	Customer-facing identity, rig model, serial number, date, and report title.	Correct rig/customer/date information supports it.
Formal energy measurement summary	Narrative summary of what was measured, why, equipment used, and test overview.	Field notes help explain unusual conditions.
Hammer Efficiency Summary table	Samples, average transferred energy, range, standard deviation, ETR, BPM.	Good analyzer files and clean intervals feed the table.
Measurement Summary page	Owner, operator, date, location, boring ID, hammer type, method, rods, equipment, ASTM methods, personnel.	Calibration log and setup details must be complete.
Exhibit A - analyzer results	Raw/printed PDA/SPT analyzer pages with graphs and collection data.	Saved data files must be accessible and tied to correct intervals.
Final SPT Test Results	N, N60, VMX, BPM, EFV, ETR, averages, standard deviation, max/min.	6-inch blow counts and correct interval context matter.
Exhibit B - equipment calibration	Analyzer/equipment calibration or compliance documentation.	Tech preserves equipment context and reports issues.
Technician training certificate	Included when applicable/available.	Only where required or appropriate.
Field notes / exceptions	Shallow interval, site condition, refusal, obscure field issue, or unusual data condition.	The tech is the primary source for these notes.

12. Report responsibility and status workflow

The calibration event moves through a status workflow. The tech mainly controls the quality of the Data Collection Complete handoff.

Status	Meaning	Exit criteria / field-tech relevance
Scheduled	Calibration event is booked but not completed.	Date, location, rig count, tech assignment, rod type, and contact information confirmed.
Data Collection Complete	Field/analyzer data has been collected.	Data files saved and transferred/handed off; calibration log complete; obscurities documented.
Report Drafting	Qualified report builder is assembling the formal package.	Report builder has files, metadata, analyzer outputs, notes, and certificates.
Needs Clarification	Report builder cannot complete package due to missing or unclear field information.	Field tech provides notes, photos, video, explanation, or corrected context.
Ready for Review	Report package is complete and ready for internal review/sign-off.	No missing pages or unresolved field issues.
Delivered	Final report delivered to customer.	Final PDF saved and delivery date recorded.

Status	Meaning	Exit criteria / field-tech relevance
Follow-Up Created	Next calibration or sales follow-up is scheduled.	Relationship/prospecting notes can support future action.

13. Report builder and customer delivery boundary

Current qualified report builders
Jonathon and Charlie are the qualified report builders and follow the same report-building standards.

- The standard tech does not send the final calibration report directly to the customer.
- Final customer delivery comes from Jonathon or Charlie.
- The standard tech should not promise pass/fail, a specific energy percentage, or same-day delivery.
- The tech should make sure Jonathon or Charlie has the files and context needed to meet the three-day delivery expectation.

14. Do-not-promise rules for report handoff

Category	Do not promise / assume	Correct behavior
Report timing	Do not promise same-day delivery unless specifically confirmed by a qualified report builder.	State the standard expectation: three days from data collection.
Report result	Do not promise the hammer will pass or predict a specific energy transfer percentage.	Data must be collected and reviewed first.
Dirty data	Do not issue or rush a report when field obscurities are not documented well enough.	Document and clarify before report building continues.
Role boundary	Do not assume someone who can collect data can build reports correctly.	Report building remains with qualified report builders.
Customer pressure	Do not let production pressure turn missing notes into a report problem.	Preserve data, document exceptions, and escalate when needed.

15. Needs Clarification workflow

A calibration event enters Needs Clarification when the report builder cannot finish because field information is missing, unclear, or inconsistent.

Clarification issue	Likely cause	Tech response
Missing depth interval	Software/file context and field sheet do not match or interval was not recorded.	Provide corrected interval if known; otherwise document uncertainty.
Missing 6-inch blow counts	Paper record incomplete.	Explain what is missing; if still on site and possible, collect another proper data set.
Questionable data without notes	Rerun/refusal/rapid advancement/sensor issue not explained.	Provide field explanation, photos/video if available, and whether data was rerun.
Sensor or equipment issue unclear	Accelerometer, cable, connector, or pulse-check issue not documented.	Explain what was checked, replaced, or escalated.
Production interval not explained	Project required non-preferred interval/frequency.	Document customer/project requirement and actual collected interval.

16. Before leaving site checklist

Closeout area	Required action	Pass standard
Data files	Confirm data files are saved on analyzer	Files can be accessed by report builder.

Closeout area	Required action	Pass standard
	hardware and handoff method is clear.	
Calibration log	Confirm one sheet per rig is complete.	No missing rig ID, intervals, LP/LE, or blow-count essentials.
Notes	Document any field obscurity or unusual condition.	Report builder can understand the event without guessing.
Photos/video	Capture useful photos and required issue video when data is affected.	Media is transferred or noted as available.
Equipment	Pack and inspect analyzer kit, cables, accelerometers, hardware, and instrumented rod.	Damage or missing items documented and reported.
Drillers	Personally thank drillers for their help.	Relationship closed professionally.
Tooling wish list	Ask whether they have tooling needs or a wish list to send back.	Useful sales/service note captured.
Shirts	Give T-shirts to people on site when available/appropriate.	Relationship-building touch completed.
Manager	Thank drilling manager for choosing Mobile Drill.	Professional closeout and prospecting conversation attempted.
Business pulse	Ask how business is going and listen for prospecting signals.	Relevant notes sent back internally.

17. Customer relationship and prospecting notes

The field closeout is also a chance to capture practical sales intelligence without turning the tech into a pushy salesperson.

- Ask whether the drillers have a tooling wish list or parts/tooling needs they want sent back.
- Listen for upcoming jobs, fleet growth, rig issues, report deadlines, DOT/government work, or competitor equipment concerns.
- Thank the drilling manager for choosing Mobile Drill.
- Ask how business is going and capture useful notes for follow-up.
- Do not promise pricing, discounts, delivery dates, calibration outcomes, or report results from the field unless approved.

18. Common mistakes

Mistake	Why it matters	Correct behavior
Leaving site with incomplete calibration log	Report builder may have to chase basic facts.	Complete one sheet per rig before closeout.
Sending analyzer files without context	Report builder may not know which rig/interval files belong to.	Send files with customer, rig, borehole, and interval notes.
Assuming software total replaces paper blow counts	Report requires 6-inch increments.	Record blow counts by 6-inch increment.
Not documenting refusal or rapid advancement	Data may be misread as normal.	Document depth, advancement, blow count, and action taken.
Failing to report sensor/equipment issue	Report builder may trust questionable data.	Document and report sensor/equipment issues.
Promising same-day report	May conflict with report-builder capacity and review needs.	Use three-day standard unless qualified report builder confirms otherwise.
Letting relationship notes disappear	Tooling/prospecting opportunities are lost.	Send back tooling wish list and business notes.

19. Training scenario

Scenario: A tech finishes calibration on one rig at a customer yard. One interval had rapid advancement, and an accelerometer was replaced with a backup after a failed pulse check. The final pulse check passed, and a clean run was collected. The customer asks if the report can be sent today because they need it for an upcoming job.

Correct trainee response should include:

- Confirm data files are saved and accessible for handoff.
- Complete the calibration log for the rig, including all intervals, LP, LE, and 6-inch blow counts.
- Document the rapid advancement and the accelerometer replacement.
- Export data by USB to work laptop and email it to the report builder, or perform the approved physical handoff if that is the current path.
- Do not promise same-day delivery unless Jonathon or Charlie confirms it.
- State that the standard report expectation is three days from data collection.
- Thank the drillers, ask about tooling needs, thank the manager, and capture any relationship/prospecting notes.

20. Knowledge check

#	Question	Answer key
1	When is the field side of a calibration job complete?	When data files, calibration log, field notes, exceptions, and handoff path are complete enough for the report builder.
2	Where is analyzer data stored?	On the SPT analyzer hardware.
3	What is the most common/easiest data handoff path?	USB export from hardware unit to work laptop, then email to report builder.
4	What paper form is used for field documentation?	Calibration log, one sheet per rig.
5	Who are the qualified report builders in current training?	Jonathon and Charlie.
6	Can a standard tech send the final report directly to the customer?	No. Final report delivery comes from Jonathon or Charlie.
7	What is the standard report delivery expectation?	Three days from data collection.
8	When is video required?	When a weird issue affects calibration data.
9	Why are field notes important?	The report builder may not have been on site and needs enough context to explain or review data.
10	What should the tech ask drillers before leaving site?	Whether they have a tooling wish list or needs to send back.
11	What status is used when the report builder cannot finish due to missing or unclear field information?	Needs Clarification.
12	What should the tech not promise about the report?	Same-day delivery, pass/fail, or specific energy transfer percentage unless properly confirmed.

21. Practical signoff checklist for Module 007

Signoff item	Pass standard	Trainer initials/date
Explains handoff purpose	Trainee explains why saved data alone is not enough.	
Ends test correctly	Trainee knows End Test / Yes makes data available for review.	
Transfers data	Trainee can describe USB-to-laptop/email handoff and office	

Signoff item	Pass standard	Trainer initials/date
	physical handoff.	
Completes calibration log	Trainee completes one sheet per rig with required values.	
Checks consistency	Trainee verifies files, depth intervals, LP, LE, sample intervals, and paper notes match.	
Documents exceptions	Trainee records refusal, rapid advancement, reruns, sensor changes, and questionable data.	
Understands report package	Trainee can name the major report package components at an awareness level.	
Follows delivery boundary	Trainee states final customer report comes from Jonathon or Charlie.	
Applies relationship closeout	Trainee thanks crew/manager and captures tooling/business notes without overpromising.	

22. SME-needed / next module inputs

No current SME item blocks Module 007 v0.1. Future refinements can add an actual redacted report package example, the exact calibration log layout, or example handoff email language.

Next module

Module 008 should cover Customer Communication and Do-Not-Promise Rules: how the technician explains calibration, report timing, data quality, results boundaries, and relationship/prospecting notes without making unauthorized commitments.

Revision history

Version	Status	Change
v0.1	Deliverable	Created Module 007 from calibration extraction worksheet, cheat sheet workflow, Modules 004-006, and SME corrections on report handoff, calibration log, photos/video, report builders, three-day delivery, field closeout, and customer relationship notes.